



Work No. 5

**Name of Work : Estimate For Repairs to Cafiteria Roof in Alliance Francaise Bangalore
Premises Thimmaiah road Vasanth Nagar Bengaluru -560 052**

It. No.	Description of items	Unit	Qty	Rate	Amount
Cafiteria Roofing					
1	Removing and resetting Mangalore tiles and replacing broken ones wherever necessary including cost of materials, labour, HOM complete as per specifications. (excluding cost of new tiles).	Sqm	11.90		
2	Supplying and fixing new Mangalore tiles on existing reepers including cost of materials, labour, HOM complete as per specifications	Sqm	3.40		
3	Dismantling A.C.Sheet roof and stacking the material within a radius of 50 meters. including cost of materials, labour, HOM complete as per specifications	Sqm	59.50		
4	Providing, fabricating and fixing profiled polyuerethane insulated roof of 1,06m width and 7,60m length sheets roof having external sheet of 0.5mm steel with powder coated finish, bottom sheet of 0.4mm steel with powder coated finish. The roofing system shall have water proof over lapping arrangement at the inter section of two sheets the fasting shall be of self tapping screws dia 6.3mm or required length with PVC head along with washer pre-painted aluminium cap unit with build in seal arrangements. The entire roof shall be firmly fasteed to the existing frame.	Sqm	59.50		
5	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per diréctions of the Engineer-in-Charge.	Kgs	607.00		
				Total	

General Secretary
Alliance francaise Bangalore

Contracor