



Work No, 5

**Name of Work : Estimate For Cafeteria Roof in Alliance Francaise Bangalore Premises  
Thimmaiah road Vasanth Nagar Bengaluru -560 052**

It. No.	Description of items	Unit	Qty	Rate	Amount
1	Removing and resetting Mangalore tiles and replacing broken ones wherever necessary including cost of materials, labour, HOM complete as per specifications. (excluding cost of new tiles).	Sqm	11.81		
2	Supplying and fixing new Mangalore tiles on existing reepers including cost of materials, labour, HOM complete as per specifications	Sqm	3.38		
3	Dismantling A.C.Sheet roof and stacking the material within a radius of 50 meters. including cost of materials, labour, HOM complete as per specifications	Sqm	59.50		
4	Providing,fabricating and fixing Profiled Poly Urethane insulated Roof(PUF Sheet) having modular density 40kg/m <sup>2</sup> and size 1.06m width and 7.60m length sheets roof having external sheet of 0.5mm steel, bottom sheet of 0.40mm steel with powder coated finish. The precoated sheet shall be of minimum 240MPa steel conforming to IS 14246 : 1995 and shal have zinc coating with minimum 120gsm as per IS 277:1992, The roofing system shall have suitable water proof over lapping arrangements and GRIHA ceritified.The fasting shall be of self tapping screws of required length with PVC head along with washer pre-painted aluminium cap unit with build in seal arrangements.The entire roof shall be firmly fastened to the existng frame including all lead and lifts, loading & unloading ,usage charges of machinery and equipments, transportation charges,labour charges and all other incidental charges etc.,complete as per standard technical detailed specifications and as directed by the Engineer in charge of work 30 mm thickness	Sqm	59.50		



General Secretary

Alliance francaise Bangalore

Contracor



5	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Kgs	509.41		
				Total	

  
 General Secretary  
 Alliance francaise Bangalore

Contractor