



Work No.6

Name of Work : Estimate For Proving Terracota tiles Flooring in Alliance Francaise Bangalore Premises Thimmaiah road Vasanth Nagar Bengaluru -560 052					
It. No.	Description of items	Unit	Qty	Rate	Amount
Terracota Tiles Flooring					
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material to the appropriate disposal area as per direction of Engineer-in-charge.	Sqm	175.03		
2	Providing and fixing of clay tiles for cladding tiles of size 230x75x10mm thick on 12mm thick cement mortar 1:3 (1 cement : 3 coarse sand) & jointed with Adhesive/cement slurry over rough plaster surface excluding cost of rough plastered surface and the surface is painted with red apex paint and black apex paint into the groves. The work includes cost of all materials, labour charges for all items of work, usage	Sqm	175.03		
				Total	

General Secretary
alliance Francaise Bangalore

Contractor